

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE - 'B'


Item-54

Name of Work:-Construction of culverts in ward no 03, Attur

SI	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHUMIREDDY DAMODAR REDDY	
				Rate	Rate in Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	27.72	236.21	Rupees Two Hundred Thirty Six and Paise Twenty One Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.3 of PWD SR 2018-19	Cum	3.96	4813.23	Rupees Four Thousand Eight Hundred Thirteen and Paise Twenty Three Only
3	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 25 / Item No. 5.6, PWD SR 2018-19	Cum	14.26	4335.87	Rupees Four Thousand Three Hundred Thirty Five and Paise Eighty Seven Only
4	KSRB 15.1.2 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:4, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications Page No. 115 / Item No. 15.2, PWD SR 2018-19	Sqm	23.76	132.08	Rupees One Hundred Thirty Two and Paise Eight Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHUMIREDDY DAMODAR REDDY	
			Rate	Rate in Words
5 KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.13, Item No. 4.6 PWD SR 2018-19	Cum	5.94	5115.12	Rupees Five Thousand One Hundred Fifteen and Paise Twelve Only
6 Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge - Data rate	Sqm	23.76	4822.02	Rupees Four Thousand Eight Hundred Twenty Two and Paise Two Only

B. Damodhar Reddy
Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.